



Betriebsdruck: 14 bar
 Prüfdruck: 22 bar

Typ	A	B	X	WW	Art.-Nr
210	520	610	Rp 1/2"	3	10740
213	820	910	Rp 1/2"	3	12677
217	1220	1310	Rp 3/4"	6	12678
221	1620	1710	Rp 3/4"	6	12679

Anzahl		Stammteil-Nr.		Index		Änderung		Name		Datum	
Stamm-Nr.		Folge-Nr.		Formal		Ari-Gr.		SAP-Nr.		CAD-Nr.	
Projekt-Nr.		Erst.		20.10.06		p.backs		2		148	
Auftr.-Nr.		Änder.		25.10.06		p.backs		-		-	
STL-Nr.		Gepr.		25.10.06		p.backs		-		-	
		Freig.		25.10.06		p.backs		M 1:1		Abm.	
										49794 Lingen Tel. 0591-7108-0 Erst. 20.10.06 p.backs Änder. 25.10.06 p.backs Gepr. 25.10.06 p.backs Freig. 25.10.06 p.backs	
Wärmetauscher CuAl Serie 2 2-Leiter 3RR Venkon										Nr.- 352425 Vers. 1	
										Zul.Abw. ISO 2768-m Revision Betrieb Bl.	